TOWN OF COOPERSTOWN IS ACCEPTING BIDS FOR REPLACEMENT OF (18) CULVERTS ON VARIOUS ROADS.

EACH CULVERT TO BE BID SEPERATLY

ANY DNR PERMITS REQUIRED ARE TO BE APPLIED FOR AND ACQUIRED BY THE CONTRACTOR. LOCATION AND SPECS ON ALL CULVERTS TO BE BID ARE AVAILABLE FROM TOWN. SUMMARY BELOW. NO END WALLS NEEDED. DUAL WALL PLASTIC ON ALL CULVERTS UNLESS COVER CAN NOT BE PROVIDED. INSTALLATION SHALL INCLUDE RESTORATION OF GRAVEL SHOULDER. BANK SLOPED 2:1 TO BOTTOM OF DITCH. TOP DRESSED IN BLACK GROUND AND RESEEDED. EROSION CONTROL MEASURES DURING AND AFTER INSTALLATION. ROADWAY TO BE PATCHED TO THREE (3) IN. OF COMPACTED COLD MIX ASPHALT. CONTRACTOR RESPONSIBLE FOR ROAD CLOSURE MEASURES AND PROPER MARKING.

CULVERT LIST:

COOPERSTOWN RD	1 - 24"X60'
DEVILS RIVER DR	1-24"X60'
FREICH RD	1 - 18"X50'
HICKORY GROVE RD	1a & 1b - 18"X60'
	1c- 24"X60'
HIDDEN VALLEY RD	1a – 18"X60'
	1b- 18"X80'
KEEHAN RD	1a– 24"X40'
	1b & 1c – 18"X40'
LUEBKE RD	1 – 18"X40'
SHULTZ RD	1a, 1b & 1c – 18"X60'
ZANDER RD	1 – 24"X60'
	1 – 24"X50'
	1-18"X50'

CONTACT DAN KASTEN FOR LOCATIONS, SPECIFICS, INSTALLATION GRADES, OR QUESTIONS. (920) 621-4237

ALL BIDS AND PROOF OF INSURANCE MUST BE RECIEVED BY 5PM MONDAY JUNE 13, 2022

MAIL (EMAIL) BIDS TO: TOWN OF COOPERSTOWN % SUE KORNELY, CLERK 15911 CTH R MARIBEL WI. 54227 TOWNOFCOOPERSTOWN1856@YAHOO.COM